

Ministry of the Environment, Conservation and Parks Ministère de l'Environnement, de la Protection de la nature et des Parcs

AMENDED ENVIRONMENTAL COMPLIANCE APPROVAL

NUMBER 8676-CWCNE8 Issue Date: January 8, 2024

Flavor Fresh Farms Ltd. 635 Mersea Road 7 Leamington, Ontario N8H 3V8

Site Location: 635 Mersea Road 7 Municipality of Leamington County of Essex, Ontario

You have applied under section 20.2 of Part II.1 of the <u>Environmental Protection Act</u>, R.S.O. 1990, c. E. 19 (Environmental Protection Act) for approval of:

expansion, usage and operation of Works, for the treatment of **sanitary** sewage from existing Phases 1 and 2 bunkhouses and new Phase 3 bunkhouse development located at the above Site Location, with treated Final Effluent discharged into a municipal drain - Cowan D&W Drain via two (2) Sewage Treatment Systems and Final Effluent disposal facilities, as follows:

Proposed Service Area

- Phase 3 bunkhouse for accommodating a total of 72 people residing on-site; and
- washroom facilities serving greenhouse/warehouse for a maximum of 25 staff.

Existing Service Area

- Phases 1 and 2 bunkhouses for accommodating a total of 144 people residing on-site; and
- washroom facilities serving greenhouse, warehouse and office for a maximum of 75 staff.

Design Capacity of the Sanitary Sewage Treatment Systems

	Prior to Completion of Construction of	Upon Completion of Construction of
	All Proposed Works	All Proposed Works
Maximum Daily Flow	40,000 cubic metres per day	60,000 cubic metres per day

Proposed Works

Sewage treatment and surface water disposal train No.2 with a design Maximum Daily Flow of 20,000 litres per

day, located adjacent to the Existing Works, for the treatment and disposal of sanitary sewage from Phase 3 bunkhouse and washroom facilities serving greenhouse and office, consisting of the following:

Preliminary Treatment System

• one (1) 6,400 litre grease interceptor, receiving sewage from kitchens located in Bunkhouse #3, and discharging into a septic/sludge tank;

Primary Treatment System

- two (2) double-compartment septic/sludge tanks (identified as Anaerobic Digesters #3 and #4), each having a volume of 18,200 litres, operating in series, receiving sewage from washroom facilities and the effluent from the grease interceptor, completed with an electro-chemical phosphorus removal unit (EC-P Unit) installed in the second compartment of the Anaerobic Digesters #4, discharging the primary effluent into a Pump Tank;
- one (1) 9,100 litre Pump Tank receiving the effluent from the Anaerobic Digester #4, equipped with duplex effluent pumps each rated at 227 litres per minute against a Total Dynamic Head (TDH) of 13.4 metres discharging into a Sludge Tank, and equipped with a Biofilter Basket with 3.4 cubic metres of Biofilter media, dosed from the pump plumbing drain hole and discharging into the Pump Tank as a closed loop pre-treatment basket;
- one (1) 18,200 litre double compartment Sludge Tank, equipped with two (2) effluent filters on the outlet, discharging via gravity into a 18,200 litre Aeration Tank;
- one (1) 18,200 litre Aeration Tank, equipped a submersible micro-bubble aerator, discharging into a 18,200 litre Clarifier Tank;
- one (1) 18,200 litre Clarifier Tank, equipped with a sludge return pump rated at 227 litres per minute against a TDH of 13.4 metres to return sludge to the inlet of the Sludge Tank, and equipped with two effluent filters on the outlet, discharging via gravity into a 20,400 litre Biofilter Dosing Tank;

Secondary Treatment System

٠

- one (1) 20,400 litre Biofilter Dosing Tank, equipped with duplex effluent pumps each rated at 302 litres per minute against a TDH of 18.9 metres, discharging into a basket in Waterloo Biofilter Tank No.4 and two baskets in Waterloo Biofilter Tank No.5, and also equipped with a Biofilter Basket with 6.1 cubic metres of Biofilter media, dosed from the pump plumbing drain hole and discharging into the Biofilter Dosing Tank as a closed loop pre-treatment basket;
 - two (2) 31,800 Waterloo Biofilter Tanks No. 4 and No. 5, operating in parallel and inter-connected to each other, each tank comprising spray units and two wire mesh baskets filled with 10.8 cubic metres of Biofilter media in each mesh basket, with one basket in Biofilter Tank No.4 and two baskets in Biofilter Tanks No.5 receiving effluent from the Biofilter Dosing Tank, and one basket in Biofilter Tank No.4 receiving effluent from Biofilter Tank No.4 as a Closed Loop Biofilter. Biofilter Tank No.4 is equipped

with simplex pump rated at 151 litres per minute against a TDH of 8.5 metres to dosing a portion of treated effluent to the Closed Loop Biofilter basket, another simplex pump for recirculating a portion of treated effluent to the inlet of Sludge Tank, and duplex pumps each rated at 302 litres per minute against a TDH of 18.9 metres to dose a portion of treatment effluent to the Sand Filter Unit in a control building;

- one (1) chemical dosing system with provision for dosing alkalinity, phosphorus removal agent, and bacteria to the Sludge Tank, Clarifier Tank, Biofilter Dosing Tank and the Closed Loop Biofilter Tank;
- one (1) Sand Filter Unit comprising clack valve to control flow rates, a 100 micron bag filter on feed line, and a sand filter consisting of a 350 millimetre diameter by 1651 millimetre high tank equipped with NextSand filtration media, with backwash discharging to the Sludge Tank and effluent discharging to UV Disinfection Units;

Disinfection

• two (2) Hallett 750 W 1" UV Disinfection Units to provide 3 log inactivation of fecal coliforms, discharging into a discharge pipe or a Diversion/Disposal tank;

Final Effluent Disposal

- one (1) discharge pipe, equipped with a flow metre, discharging the Final Effluent to a municipal drain known as Cowan D&W Drain;
- one (1) Final Effluent Sampling Point No.2 located on the discharge pipe in control building, downstream of UV disinfection units;
- one (1) 25,000 litre Diversion/Disposal tank, to receive treated effluent from the UV disinfection units if discharge to ditch is temporarily not possible; and

Miscellaneous

• including all other mechanical system, electrical system, instrumentation and control system, piping, pumps, valves and appurtenances essential for the proper, safe and reliable operation of the Proposed Works in accordance with this Approval, in the context of process performance and general principles of wastewater engineering only.

Existing Works

Sewage treatment and surface disposal train No.1 with a design Maximum Daily Flow 40,000 litres per day, for the treatment and disposal of sanitary sewage from Phases 1 and 2 bunkhouses, and form washroom facilities serving greenhouse/warehouse and office, consisting of the following:

Preliminary Treatment System

• one (1) 4,050 litre Grease Interceptor No.1, receiving sewage from Bunkhouse #1 kitchens, and

discharging into an existing septic tank;

• one (1) 6,400 litres Grease Interceptor No.2, receiving sewage from the kitchens located within Bunkhouse #2, discharging into a 18,200 litre septic/sludge tank;

Primary Treatment System

- one (1) 29,500 litre Septic Tank, receiving sewage from Bunkhouse #1 washrooms and the effluent from the Grease Interceptor No.1, discharging into the Pump Tank #1;
- two (2) septic/sludge tanks septic/sludge tanks (identified as Anaerobic Digesters #1 and #2), each having a volume of 18,200 litres, operating in series, receiving sewage from washrooms of new bunkhouse and the effluent from the Grease Interceptor No.2, discharging the primary effluent into a Pump Tank #2;
- one (1) 9,100 litre Pump Tank #1, equipped with duplex effluent pumps, discharging into a 31,800 litre Sludge Tank;
- one (1) 9,100 litre Pump Tank #2, equipped with duplex effluent pumps, discharging into the 31,800 litre Sludge Tank;
- one (1) 31,800 litre Sludge Tank, receiving sewage from office/greenhouse/warehouse washrooms and the effluent from the Pump Tanks #1 and #2, discharging into an aeration tank;
- one (1) 31,800 litre Aeration Tank, equipped with aeration system including two micro-bubble aerators, discharging into a 31,800 litre clarifier tank;
- one (1) 31,800 litre Clarifier Tank, equipped with a sludge return pump to return sludge to the inlet of the Sludge Tank, and equipped with two effluent filters on the outlet, discharging via gravity into a 40,000 litre Biofilter dosing tank;
- one (1) 40,000 litre Biofilter Dosing Tank, equipped with duplex effluent pumps, discharging into a Waterloo Biofilter Treatment System;

Secondary Treatment System

• one (1) Waterloo Biofilter Treatment System consisting of three (3) 45,000 litre Biofilter Treatment Tanks (Biofilter Tanks No.1, No. 2 and No.3), each comprising spray units and three (3) mesh baskets filled with Biofilter media, with the tanks hydraulically connected by under drains, with one basket in Biofilter Tank No.1 and three baskets in Biofilter Tanks No.2 and No. 3 receiving effluent from the Biofilter Dosing Tank, and two baskets in Biofilter Tank No.1 receiving effluent from Biofilter Tank No.1 as a Closed Loop Biofilter. Biofilter Tank No.1 is equipped with simplex pump to dosing a portion of treated effluent to the Closed Loop Biofilter baskets, another simplex pump for recirculating to the inlet of Sludge Tank, and duplex pumps discharging treated effluent into a sand filter;

- one (1) chemical dosing system with provision for dosing alkalinity, phosphorus removal agent, and bacteria to the existing Septic Tank, Septic/Sludge Tank #1, Clarifier Tank, and Biofilter Dosing Tank;
- one Sand Filter consisting of a 350 millimetre diameter by 1651 millimetre high tank equipped with NextSand filtration media, 100 micron bag filter on feed line, and clack valve to control flow rates, with backwash discharging to the Sludge Tank and effluent discharging to Ultraviolet (UV) Disinfection units ;

Disinfection

• two (2) Hallett 30 1.5" UV Disinfection Units to provide 3 log inactivation of fecal coliforms, discharging into a discharge pipe or a Diversion/Disposal Tank;

Final Effluent Disposal

- one (1) discharge pipe discharging Final Effluent to a municipal drain knowns as Cowan D&W Drain;
- one (1) Final Effluent Sampling Point No.1 located on the discharge pipe;
- one (1) 50,000 litre Diversion/Disposal Tank, to receive treated effluent from the UV disinfection units if discharge to ditch is temporarily not possible; and

Miscellaneous

• including all other mechanical system, electrical system, instrumentation and control system, piping, pumps, valves and appurtenances essential for the proper, safe and reliable operation of the Existing Works in accordance with this Approval, in the context of process performance and general principles of wastewater engineering only.

All in accordance with the submitted supporting documents in Schedule A.

For the purpose of this environmental compliance approval, the following definitions apply:

- 1. "Approval" means this entire Environmental Compliance Approval and any Schedules attached to it;
- 2. "BOD5" (also known as TBOD5) means five day biochemical oxygen demand measured in an unfiltered sample and includes carbonaceous and nitrogenous oxygen demands;
- 3. "CBOD5" means five day carbonaceous (nitrification inhibited) biochemical oxygen demand measured in an unfiltered sample;
- 4. "Director" means a person appointed by the Minister pursuant to section 5 of the EPA for the purposes of Part II.1 of the EPA;
- 5. "District Manager" means the District Manager of the Sarnia/Windsor District Office;

- 6. "E. coli " refers to coliform bacteria that possess the enzyme beta-glucuronidase and are capable of cleaving a fluorogenic or chromogenic substrate with the corresponding release of a fluorogen or chromogen, that produces fluorescence under long wavelength (366 nm) UV light, or color development, respectively. Enumeration methods include tube, membrane filter, or multi-well procedures. Depending on the method selected, incubation temperatures include 35.5 + 0.5 °C or 44.5 + 0.2 °C (to enumerate thermotolerant species). Depending on the procedure used, data are reported as either colony forming units (CFU) per 100 mL (for membrane filtration methods) or as most probable number (MPN) per 100 mL (for tube or multi-well methods);
- 7. "EPA" means the Environmental Protection Act, R.S.O. 1990, c. E.19;
- 8. "Existing Works" means those portions of the Works included in the Approval that have been constructed previously;
- 9. "Final Effluent" means effluent that is discharged to the environment through the approved effluent disposal facilities, that are required to meet the compliance limits stipulated in the Approval for the Sewage Treatment Plant at the Final Effluent sampling point(s);
- 10. "Grab Sample" or "Grab" means an individual sample of at least 1000 millilitres collected in an appropriate container at a randomly selected time over a period of time not exceeding 15 minutes;
- 11. "Influent" means flows to the Sewage Treatment Systems from the collection system;
- 12. "Licensed Engineering Practitioner" means a person who holds a licence, limited licence or temporary licence under the *Professional Engineers Act,* R.S.O. 1990, c. P.28;
- 13. "Maximum Daily Flow" (also referred to as Peak Daily Flow Rate or Maximum Day Flow) means the largest volume of flow to be received during a one-day period for which the sewage treatment process unit or equipment is designed to handle;
- 14. "Ministry" means the ministry of the government of Ontario responsible for the EPA and OWRA and includes all officials, employees or other persons acting on its behalf;
- 15. "Monthly Average Effluent Concentration" is the mean of all Single Sample Results of the concentration of a contaminant in the Final Effluent sampled or measured during a calendar month;
- 16. "Monthly Geometric Mean Density" is the mean of all Single Sample Results of *E.coli* measurement in the samples taken during a calendar month, calculated and reported as per the methodology specified in **Schedule D**;
- 17. "Normal Operating Condition" means the condition when all unit process(es), excluding Preliminary Treatment System, in a treatment train is operating within its design capacity;
- 18. "Operating Agency" means the Owner, or the person or entity that is authorized by the Owner for the

management, operation, maintenance, or alteration of the Works in accordance with this Approval;

- 19. "Owner" means Flavor Fresh Farms Ltd., including any successors and assignees;
- 20. "OWRA" means the Ontario Water Resources Act, R.S.O. 1990, c. O.40;
- 21. "Preliminary Treatment System" means all facilities in the Sewage Treatment Plant associated with screening and grit removal;
- 22. "Primary Treatment System" means all facilities in the Sewage Treatment Plant associated with the primary sedimentation unit process and includes chemically enhanced primary treatment;
- 23. "Proposed Works" means those portions of the Works included in the Approval that are under construction or to be constructed;
- 24. "Secondary Treatment System" means all facilities in the Sewage Treatment Plant associated with biological treatment, secondary sedimentation and phosphorus removal unit processes;
- 25. "Sewage Treatment Plant" means all the facilities related to sewage treatment within the sewage treatment plant site excluding the Final Effluent disposal facilities;
- 26. "Single Sample Result" means the test result of a parameter in the effluent discharged on any day, as measured by a probe, analyzer or in a composite or grab sample, as required;
- 27. "Works" means the approved sewage works, and includes Proposed Works and Existing Works.

You are hereby notified that this environmental compliance approval is issued to you subject to the terms and conditions outlined below:

TERMS AND CONDITIONS

1. GENERAL PROVISIONS

- 1. The Owner shall ensure that any person authorized to carry out work on or operate any aspect of the Works is notified of this Approval and the terms and conditions herein and shall take all reasonable measures to ensure any such person complies with the same.
- 2. The Owner shall design, construct, operate and maintain the Works in accordance with the conditions of this Approval.
- 3. Where there is a conflict between a provision of any document referred to in this Approval and the conditions of this Approval, the conditions in this Approval shall take precedence.

2. CHANGE OF OWNER AND OPERATING AGENCY

- 1. The Owner shall notify the District Manager and the Director, in writing, of any of the following changes within **thirty (30) days** of the change occurring:
 - a. change of address of Owner;
 - b. change of Owner, including address of new owner;
 - c. change of partners where the Owner is or at any time becomes a partnership, and a copy of the most recent declaration filed under the *Business Names Act,* R.S.O. 1990, c. B.17 shall be included in the notification;
 - d. change of name of the corporation and a copy of the most current information filed under the *Corporations Information Act,* R.S.O. 1990, c. C.39 shall be included in the notification.
- The Owner shall notify the District Manager, in writing, of any of the following changes within thirty (30) days of the change occurring:
 - a. change of address of the Operating Agency;
 - b. change of the Operating Agency, including address of the new Operating Agency.
- 3. In the event of any change in ownership of the Works, the Owner shall notify the succeeding owner in writing, of the existence of this Approval, and forward a copy of the notice to the District Manager.
- 4. The Owner shall ensure that all communications made pursuant to this condition refer to the number of this Approval.

3. CONSTRUCTION OF PROPOSED WORKS

- 1. All Proposed Works in this Approval shall be constructed and installed and must commence operation within **five (5) years** of issuance of this Approval, after which time the Approval ceases to apply in respect of any portions of the Works not in operation. In the event that the construction, installation and/or operation of any portion of the Proposed Works is anticipated to be delayed beyond the time period stipulated, the Owner shall submit to the Director an application to amend the Approval to extend this time period, at least six (6) months prior to the end of the period. The amendment application shall include the reason(s) for the delay and whether there is any design change(s).
- 2. The Owner shall ensure that the treatment technologies are installed in accordance with the manufacturer's installation manual.
- 3. Upon completion of construction of the Proposed Works, the Owner shall prepare and submit a written statement to the District Manager, certified by a Licensed Engineering Practitioner, that the Proposed

Works is constructed in accordance with this Approval.

- 4. One (1) week prior to the commencement of the operation of the Proposed Works, the Owner shall notify the District Manager (in writing) of the pending start-up date.
- 5. Within one (1) year of completion of construction of the Proposed Works, a set of record drawings of the Works shall be prepared or updated. These drawings shall be kept up to date through revisions undertaken from time to time and a copy shall be readily accessible for reference at the Works.

4. DESIGN OBJECTIVES

- 1. The Owner shall design and undertake everything practicable to operate the Sewage Treatment Plant in accordance with the following objectives:
 - a. Final Effluent is essentially free of floating and settleable solids and does not contain oil or any other substance in amounts sufficient to create a visible film or sheen or foam or discolouration on the receiving waters.
 - b. The maximum flow to the sewage treatment and surface water disposal train No.1 (Phases 1 and 2) is within the Maximum Daily Flow of **40,000 litres per day**.
 - c. The maximum flow to the sewage treatment and surface water disposal Train No.2 (Phase 3) is within the Maximum Daily Flow of **20,000 litres per day**.

5. COMPLIANCE LIMITS

- 1. The Owner shall operate and maintain Sewage Treatment Plant such that compliance limits for the Final Effluent parameters listed in the table included in **Schedule B** are met.
- 2. The Owner shall operate and maintain the Sewage Treatment Plant such that the Final Effluent is disinfected continuously year-round, or during operation for seasonal operation.
- 3. The Owner shall cease discharge of any non-compliant effluent to the receiver within 24 hours under the following conditions, until the Sewage Treatment Plant returns to compliance.
 - a. Upon request by the District Manager.
 - b. Should the concentration of Total Ammonia Nitrogen (TAN) in the Final Effluent exceed 4.0 milligrams per litre during the summer (May 01 to October 31) or 6.0 milligrams per litre during the winter (November 01 to April 30) during the operational life of the Sewage Treatment Plant, including start-up and commissioning, the Owner shall notify the District Manager pursuant to subsection 2 of Condition 8 (regarding reporting) and stop discharging to the receiver within twenty-four (24) hours.
- 4. Under the cease-discharging conditions pursuant to above subsections 3.a. or 3.b., the Owner shall

implement the contingency measures pursuant to subsection 2.f. of Condition 6 (regarding operation and maintenance), and ensure the non-compliant effluent be either recirculated through the treatment system for re-treatment for compliance, or be hauled off-site to an approved waste disposal site by a registered waste hauler.

5. Upon the Sewage Treatment Plant returning to compliance, the Owner shall ensure the District Manager be notified prior to discharge resumption.

6. OPERATION AND MAINTENANCE

- 1. The Owner shall ensure that, at all times, the Works and the related equipment and appurtenances used to achieve compliance with this Approval are properly operated and maintained. Proper operation and maintenance shall include effective performance, adequate staffing and training, including training in all procedures and other requirements of this Approval and the OWRA and relevant regulations made under the OWRA, process controls and alarms and the use of process chemicals and other substances used in the Works.
- 2. The Owner shall prepare/update the operations manual for the Works within six (6) months of completion of construction of the Proposed Works, that includes, but not necessarily limited to, the following information:
 - a. operating procedures for the Works under Normal Operating Conditions;
 - b. inspection programs, including frequency of inspection, for the Works and the methods or tests employed to detect when maintenance is necessary;
 - c. repair and maintenance programs, including the frequency of repair and maintenance for the Works;
 - d. procedures for the inspection and calibration of monitoring equipment;
 - e. operating procedures for the Works to handle situations outside Normal Operating Conditions and emergency situations such as a structural, mechanical or electrical failure, or an unforeseen flow condition;
 - f. a spill prevention control and countermeasures plan, consisting of contingency plans and procedures for dealing with equipment breakdowns, potential spills and any other abnormal situations, including notification of the Spills Action Centre (SAC) and District Manager;
 - g. procedures for receiving, responding and recording public complaints, including recording any follow-up actions taken.
- 3. The Owner shall maintain an up to date operations manual and make the manual readily accessible for reference at the Works for the operational life of the Works. Upon request, the Owner shall make the manual available to Ministry staff.

- 4. The Owner shall ensure that the Operating Authority possesses the level of training and experience sufficient to allow safe and environmentally sound operation of the Works.
- 5. The Owner shall ensure the Grease Interceptors be cleaned out at least once per year, or more frequently as determined by the Works operator, for removal of fats, oil and grease from the kitchen wastewater prior to discharging the sewage to the flow equalization tanks.
- 6. The Owner shall have a valid written agreement with a hauler who is in possession of a Waste Management Systems Approval, for the treatment and disposal of the sludge generated from the Works, at all times during operation of the Works.
- 7. The Owner shall maintain a logbook to record the results of all inspections, repair and maintenance undertaken, calibrations, monitoring and spill response or contingency measures undertaken and shall make the logbook available for inspection by Ministry staff. The logbook shall include the following:
 - a. the name of the operator making the entry; and
 - b. the date and results of each inspection, repair, maintenance, calibration, monitoring, spill response and contingency measure.

7. MONITORING AND RECORDING

- 1. The Owner shall, upon commencement of operation of the Works, carry out a scheduled monitoring program of collecting samples at the required sampling points, at the frequency specified or higher, by means of the specified sample type and analyzed for each parameter listed in the tables under the monitoring program included in **Schedule C** and record all results, as follows:
 - a. all samples and measurements are to be taken at a time and in a location characteristic of the quality and quantity of the sewage stream over the time period being monitored.
 - b. definitions and preparation requirements for each sample type are included in document referenced in Paragraph 2.b.
 - c. definitions for frequency:
 - i. Weekly means once every week
 - ii. Monthly means once every month
 - iii. Annually means once every year
 - d. a schedule of the day of the week/month for the scheduled sampling shall be created. The sampling schedule shall be revised and updated every year through rotation of the day of the week/month for the scheduled sampling program, except when the actual scheduled monitoring frequency is three (3)

or more times per week.

- e. The measurement frequencies specified in Schedule C in respect to any parameter may, after two (2) years of monitoring in accordance with this Condition, be modified by the Director in writing.
- 2. The methods and protocols for sampling, analysis and recording shall conform, in order of precedence, to the methods and protocols specified in the following documents and all analysis shall be conducted by a laboratory accredited to the ISO/IEC:17025 standard or as directed by the District Manager:
 - a. the Ministry's Procedure F-10-1, "Procedures for Sampling and Analysis Requirements for Municipal and Private Sewage Treatment Works (Liquid Waste Streams Only), as amended;
 - b. the Ministry's publication "Protocol for the Sampling and Analysis of Industrial/Municipal Wastewater Version 2.0" (January 2016), PIBS 2724e02, as amended;
 - c. the publication "Standard Methods for the Examination of Water and Wastewater", as amended; and
 - d. for any parameters not mentioned in the documents referenced in Paragraphs 3.a, 3.b and 3.c, the written approval of the District Manager shall be obtained prior to sampling.
- 3. The Owner shall monitor and record the flow rate and daily quantity using flow measuring devices or other methods of measurement as approved below calibrated to an accuracy within plus or minus 15 per cent (+/- 15%) of the actual flowrate of the following:
 - a. Influent flow to the Sewage Treatment Plant by instrumentations/pumping rates;
 - b. Final Effluent discharged from the Sewage Treatment Plant by continuous flow measuring devices.
- 4. The Owner shall retain for a minimum of five (5) years from the date of their creation, all records and information related to or resulting from the monitoring activities required by this Approval.

8. REPORTING

- 1. One week prior to the start up of the operation of the Proposed Works, the Owner shall notify the District Manager (in writing) of the pending start up date.
- 2. The Owner shall report to the District Manager orally as soon as possible any non-compliance with the effluent compliance limits, and in writing within seven (7) days of non-compliance.
- 3. In addition to the obligations under Part X of the EPA and O. Reg. 675/98 (Classification and Exemption of Spills and Reporting of Discharges) made under the EPA, the Owner shall, within fifteen (15) days of the occurrence of any reportable spill as provided in Part X of the EPA and O. Reg. 675/98, submit a full written report of the occurrence to the District Manager describing the cause and discovery of the spill, clean-up and recovery measures taken, preventative measures to be taken and a schedule of implementation.

- 4. The Owner shall, upon request, make all manuals, plans, records, data, procedures and supporting documentation available to Ministry staff.
- 5. The Owner shall prepare performance reports on a calendar year basis and submit to the District Manager in an electronic format by **June 30** of the calendar year following the period being reported upon. The reports shall contain, but shall not be limited to, the following information pertaining to the reporting period:
 - a. a summary and interpretation of all Influent monitoring data, and a review of the historical trend of the sewage characteristics and flow rates;
 - b. a summary and interpretation of all Final Effluent monitoring data, including concentration, flow rates, and a comparison to the design objectives and compliance limits in this Approval, including an overview of the success and adequacy of the Works;
 - c. a summary of all operating issues encountered and corrective actions taken;
 - d. a summary of all normal and emergency repairs and maintenance activities carried out on any major structure, equipment, apparatus or mechanism forming part of the Works;
 - e. a summary of any effluent quality assurance or control measures undertaken;
 - f. a summary of the calibration and maintenance carried out on all Influent, and Final Effluent monitoring equipment to ensure that the accuracy is within the tolerance of that equipment as required in this Approval or recommended by the manufacturer;
 - g. a description of efforts made and results achieved in meeting the design objectives outlined in Condition 4;
 - h. a tabulation of the volume of sludge generated, an outline of anticipated volumes to be generated in the next reporting period and a summary of the locations to where the sludge was disposed;
 - i. a summary of any complaints received and any steps taken to address the complaints;
 - j. a summary of all other situations outside Normal Operating Conditions and spills within the meaning of Part X of EPA and abnormal discharge events;
 - k. any changes or updates to the schedule for the completion of construction and commissioning operation of major process(es) / equipment groups in the Proposed Works; and
 - 1. any other information the District Manager requires from time to time.

Schedule A

1. Application for Environmental Compliance Approval February 28, 2023 and received on March 21, 2023, submitted by Dean Mastronardi, President, Flavor Fresh Farms Ltd., for the amendment of existing ECA Number 4870-BZ5NFD for an additional sanitary sewage treatment and surface water disposal train serving Phase 3 bunkhouse/greenhouse development, including design brief, engineering drawings and specifications.

Schedule B

T mai Ellittetit Compitance Ellittis		
Effluent Parameter	Monthly Average Effluent Concentration* ¹ Limits (maximum unless otherwise indicated)	
	Summer	Winter
	(May 01 to October 31)	(November 01 to April 30)
Column 1	Column 2	Column 3
CBOD5	10.0 mg/L*^2	15.0 mg/L
Total Suspended Solids (TSS)	10.0 mg/L	15.0 mg/L
Total Phosphorus (TP)	0.3 mg/L	0.3 mg/L
Total Ammonia Nitrogen (TAN)* ³	2.0 mg/L	3.0 mg/L
E. coli.	100 CFU/100 millilitres* ⁴	100 CFU/100 millilitres* ⁴

Final Effluent Compliance Limits

Note*¹: The limit of *E.coli*. is for monthly Geometric Mean Density.

Note*²: mg/L means milligrams per litre.

Note*³: During commissioning stage, six (6) months after the date of start-up, an interim compliance limit applies for the Total Ammonia Nitrogen (TAN) as: 4.0 mg/L during Summer (May 01 to October 31), or 6.0 mg/L during Winter (November 01 to April 30).

Note*⁴: If the MPN method is utilized for *E. coli* analysis, the limit shall be 100 MPN/100 millilitres.

Schedule C - Monitoring Program

Sample locations	Two (2) sampling points as follows:
	 Sewage Treatment and Surface Disposal System No.1 (Phases 1 and 2) - one of the septic/sludge tanks (Anaerobic Digester #1 or #2); and Sewage Treatment and Surface Disposal System No.2 (Phase 3) - one of the septic/sludge tanks (Anaerobic Digester #1 or #2).
Frequency	Monthly
Sample Type	Grab
Parameters	BOD5, Total Suspended Solids, Total Phosphorus, Total Ammonia
	Nitrogen, Total Kjeldahl Nitrogen, pH

Table C-1 Influent Monitoring

Sample location	Two (2) sampling points as follow:		
	1) Sewage treatment and surface water disposal train No.1 (Phases 1 and		
	2) - Final Effluent Sampling Point No.1 at discharge line from the UV		
	Disinfection Units, prior to discharging into the Cowan D&W Drain;		
	and		
	2) Sewage treatment and surface water disposal train No.2 (Phase 3) -		
	Final Effluent Sampling Point No.2 at discharge line from the UV		
	Disinfection Units, prior to discharging into the Cowan D&W Drain		
Frequency	Weekly		
Sample Type	Minimum 8-hour Composite (except E. Coli., pH, and Temperature)		
Parameters	CBOD5, Total Suspended Solids, Total Ammonia Nitrogen, Total		
	Phosphorus, E. coli. (grab), pH*(grab/probe/analyzer), and		
	Temperature*(grab/probe/analyzer)		

Table C-2 Final Effluent Monitoring

Note*: pH and temperature of the Final Effluent shall be determined in the field at the time of sampling for Total Ammonia Nitrogen.

Parameters	Sample Type	Minimum Frequency
Total Solids	Grab	Annually
Total Phosphorus	Grab	Annually
Total Ammonia Nitrogen	Grab	Annually
Nitrate as Nitrogen	Grab	Annually
Metal Scan - Arsenic - Cadmium - Cobalt - Chromium - Copper - Lead - Mercury - Molybdenum - Nickel - Potassium - Selenium - Zinc	Grab	Annually

 Table C-3 Sludge/Biosolids Sampling

 Sampling location: Sludge Storage Tank and Septic/Sludge Tank, as one combined sample

Schedule D

Methodology for Calculating and Reporting Monthly Geometric Mean Density

Geometric mean is defined as the n^{th} root of the product of n numbers. In the context of calculating Monthly Geometric Mean Density for *E. coli*, the following formula shall be used:

$$\sqrt[n]{x_1x_2x_3\cdots x_n}$$

in which,

"n " is the number of samples collected during the calendar month; and

"*x* " is the value of each Single Sample Result.

For example, four weekly grab samples were collected and tested for *E. coli* during the calendar month. The *E. coli* densities in the Final Effluent were found below:

Sample Number	E. coli Densities* (CFU/100 mL)
1	10
2	100
3	300
4	50

The Geometric Mean Density for these data:

$\sqrt[4]{10 \times 100 \times 300 \times 50} = 62$

*If a particular result is zero (0), then a value of one (1) will be substituted into the calculation of the Monthly Geometric Mean Density. If the MPN method is utilized for E. coli analysis, values in the table shall be MPN/100 mL.

The reasons for the imposition of these terms and conditions are as follows:

- 1. Condition 1 regarding general provisions is imposed to ensure that the Works are constructed and operated in the manner in which they were described and upon which approval was granted.
- 2. Condition 2 regarding change of Owner and Operating Authority is included to ensure that the Ministry records are kept accurate and current with respect to ownership and Operating Authority of the Works and to ensure that subsequent owners of the Works are made aware of the Approval and continue to operate the Works in compliance with it.
- 3. Condition 3 regarding construction of Proposed Works/record drawings is included to ensure that the Works are constructed in a timely manner so that standards applicable at the time of Approval of the Works are still applicable at the time of construction to ensure the ongoing protection of the environment, and that prior to the commencement of construction of the portion of the Works that are approved in principle only, the Director will have the opportunity to review detailed design drawings, specifications and an engineer's report containing detailed design calculations for that portion of the Works, to determine capability to comply with the Ministry's requirements stipulated in the terms and conditions of the Approval, and also ensure that the Works are constructed in accordance with the Approval and that record drawings of the Works "as constructed" are updated and maintained for future references.
- 4. Condition 4 regarding design objectives is imposed to establish non-enforceable design objectives to be used as a mechanism to trigger corrective action proactively and voluntarily before environmental impairment occurs.
- 5. Condition 5 regarding compliance limits is imposed to ensure that the Final Effluent discharged from the Works to the environment meets the Ministry's effluent quality requirements.
- 6. Condition 6 regarding operation and maintenance is included to require that the Works be properly operated, maintained, funded, staffed and equipped such that the environment is protected and deterioration, loss, injury or damage to any person or property is prevented. As well, the inclusion of a comprehensive operations manual governing all significant areas of operation, maintenance and repair is prepared, implemented and kept up-to-date by the Owner. Such a manual is an integral part of the operation of the Works. Its compilation and use should assist the Owner in staff training, in proper plant operation and in identifying and planning for contingencies during possible abnormal conditions. The manual will also act as a benchmark for Ministry staff when reviewing the Owner's operation of the Works.
- 7. Condition 7 regarding monitoring and recording is included to enable the Owner to evaluate and demonstrate the performance of the Works, on a continual basis, so that the Works are properly operated and maintained at a level which is consistent with the design objectives and compliance limits.

8. Condition 8 regarding reporting is included to provide a performance record for future references, to ensure that the Ministry is made aware of problems as they arise, and to provide a compliance record for this Approval.

Upon issuance of the environmental compliance approval, I hereby revoke Approval No(s). 4870-BZ5NFD issued on March 31, 2021.

In accordance with Section 139 of the *Environmental Protection Act*, you may by written notice served upon me and the Ontario Land Tribunal within 15 days after receipt of this notice, require a hearing by the Tribunal. Section 142 of the *Environmental Protection Act* provides that the notice requiring the hearing ("the Notice") shall state:

- a. The portions of the environmental compliance approval or each term or condition in the environmental compliance approval in respect of which the hearing is required, and;
- b. The grounds on which you intend to rely at the hearing in relation to each portion appealed.

Pursuant to subsection 139(3) of the *Environmental Protection Act*, a hearing may not be required with respect to any terms and conditions in this environmental compliance approval, if the terms and conditions are substantially the same as those contained in an approval that is amended or revoked by this environmental compliance approval.

The Notice should also include:

- 1. The name of the appellant;
- 2. The address of the appellant;
- 3. The environmental compliance approval number;
- 4. The date of the environmental compliance approval;
- 5. The name of the Director, and;
- 6. The municipality or municipalities within which the project is to be engaged in.

And the Notice should be signed and dated by the appellant.

This Notice must be served upon:

Registrar*		The Director appointed for the purposes of Part II.1 of
Ontario Land Tribunal		the Environmental Protection Act
655 Bay Street, Suite 1500	and	Ministry of the Environment, Conservation and Parks
Toronto, Ontario	and	135 St. Clair Avenue West, 1st Floor
M5G 1E5		Toronto, Ontario
OLT.Registrar@ontario.ca		M4V 1P5

* Further information on the Ontario Land Tribunal's requirements for an appeal can be obtained directly from the Tribunal at: Tel: (416) 212-6349 or 1 (866) 448-2248, or www.olt.gov.on.ca

The above noted activity is approved under s.20.3 of Part II.1 of the *Environmental Protection Act*. DATED AT TORONTO this 8th day of January, 2024

Fariha Pannu.

Fariha Pannu, P.Eng. Director appointed for the purposes of Part II.1 of the *Environmental Protection Act*

NH/

- c: Area Manager, MECP Windsor Area Office
- c: District Manager, MECP Sarnia District Office Sandra Swanton, K. Smart Associates Limited